

Instructions inside pack

23/11/2009

# Kinver 33

3590x(3590)5090

34mm log

**NO OTHER PARTS REQUIRED**

**CHECK ALL PARTS BEFORE ASSEMBLY  
OR EMPLOYING TRADESPEOPLE**



Instructions inside pack

23/11/2009

# Kinver 33

3590x(3590)5090

34mm log

**NO OTHER PARTS REQUIRED**

**CHECK ALL PARTS BEFORE ASSEMBLY  
OR EMPLOYING TRADESPEOPLE**



R2

# Instruction pack

14/01/2010

## Kinver 33

3590x(3590)5090

34mm log

**NO OTHER PARTS REQUIRED**

**CHECK ALL PARTS BEFORE ASSEMBLY  
OR EMPLOYING TRADESPEOPLE**

# DELIVERY DRAWING SET AND INSTRUCTIONS

**IMPORTANT INFORMATION** you will need to quote this and your order no in all correspondence

Building: **Kinver 33**  
 Building Size: **3590x(3590)5090**  
 Date: **14-Jan-10**  
 Revision no **R2**

**34mm log**

**PLEASE QUOTE PART CODE  
WHERE STATED**



Log	Quantity
A	40
A1	2
A2	1
A3	1
C	7
C1	1
D	30
E	8
F	8
G	1
H	1
I	2
J	1
K	1
V1	6
v1t	2
v2	4
v2b	2
v2t	2
v3	6
v6	30
v6t	2
0	0
<b>SPARE LOGS</b>	
A	1
B	1
F	1

JOINERY -See instructions	
DOOR	Quantity
E-SD5	1
WINDOW	Quantity
E-W4-D -Fr	2
E-W4-I	4
W4-W	W4-W

FRAME  
INSERT  
SEAL KIT

Pressure Treated Floor Bearers	
Length	Quantity
3380	11
Pressure Treated Floor joiners	
Floor Boards 110x20 T&G	
Length	Quantity
3330	31

Always a couple of extra floor and roof boards supplied

\* Angled eaves edging,eaves fascias & roof edgings may be supplid in shorter lengths

EXTRAS	SIZE-mm	code	LENGTH-mm	QTY
skirting	25x40	SK	2300	1
skirting	25x40	SK	500	1
skirting	25x40	SK	3400	3
Fascia	165X30	FC	2050	2 sets
* Roof Edging	44X70	RE	4090	2
* Angled Eaves Edging	44X24	AE	4090	2
* eaves fascias	19x70	SF	4090	2
DECK BEARERS	34 X 60 PT		1500	9
DECK BOARDS	120x28		3390	12
V11 CAP	95x30	V11	655	2
V12 CNR CAP	165X255	V12		4
V13 JOINER		V13	715	4
V14 CAP	95x30	V14	1265	2

ROOF JOISTS	120x40
5	QTY

Gable sets see drawings	
2	QTY

Roof Boards 110x20 T&G	
Length	Quantity
2000	76

Felt	Quantity
Heavy Duty/ Tiles	Quantity
Black tiles	6PKS & 18 STRIPS

Glass	E- Georgian 268x373
Type	Quantity
Tough	22

nail bag	door handles
1 bag	1 set


**Please retain for future reference  
keep all parts dry**

**Check all parts before assembly-Inspect before employing tradespeople**

E-W4-D      WINDOW  
INNER FRAME ASSEMBLY

Window  
inner frame

WA, WB, WT  
25xlog thickness  
WM  
51xLog  
thickness  
(2 pieces fixed  
together)




SCREW HERE

E-W4-D WINDOW

OUTER FRAME ASSEMBLY

TOP



**SHIRE**  
BUILT AROUND OUR REPUTATION



# SHIRE

BUILT AROUND OUR REPUTATION



Completed Kinver

## Tools required

- . Hammer
- . Rubber mallet
- . Spirit level
- . Stepladder
- . Battery-powered drill/screwdriver
- . 8mm drill
- . 3mm drill
- . Tape measure
- . Gloves
- . Sharp knife and saw
- . string

## IMPORTANT!

**Check all components before commencing with the construction of your Kinver**

1. Keep all timber dry or your building will not fit together.
2. We also recommend that you seal the corner log joints with silicone sealant (not supplied).
3. We recommend a minimum of two people required for assembly.
4. Read through all the instructions before constructing your pine lodge.
5. You will see there is a set of lettered drawings showing each side of the building. You will find these letters printed at one end of each log or in the slot.

## PLEASE NOTE

Wood is a natural product and is therefore prone to changes in appearance, including some warping, movement and splitting, particularly during unusual climatic conditions (long hot or wet spells of weather). As a natural occurrence this is not covered by a guarantee.

## Assembly of Kinver 33 pine lodge ©

Thank you and congratulations on the purchase of your Shire pine lodge. We believe that this product will give you many years of excellent service. This is a natural product manufactured to a high standard therefore if you have any queries or experience any difficulties then please contact our customer service hotline on **01945 46 89 10 01945 46 89 11 01945 46 89 12**  
Normal office hours: 8.30am to 5.00pm Monday to Friday. Answer phone all other times.

## Preparation of base

Prior to assembly a suitable perfectly flat concrete base must be provided

**Actual floor area 3590 mm x 5090 mm inc terrace inc returns .**

Building size 3590x3590

It should be at least the same size as the main building without the returns that stick out at the corners (180mm less than the external dimensions on stable ground or the same size as the external dimensions including returns on unstable ground- consult a local expert for advice. It should have a very slight fall to prevent water laying on it. We do not recommend slab and / or shingle bases as an uneven base or subsequent settling will cause excessive strain and may damage your building and invalidate your warranty.

## Treatment/care of your pine lodge

All timber must be dry to apply the timber treatment.

Treat with a suitable decorative wood finish immediately. We recommend that you treat the door and window glazing rebates and beading with a top quality timber treatment before assembly and treat the entire building as soon as assembly is complete, we further recommend that all pieces are treated and again within 3 months of assembly and again at least annually or as frequently as the instructions on the product used recommends.

**Note** the back of the door and window units unscrew so they can be removed for painting We would also remind you that you would rarely (if ever) be able to re-treat the underside of the floor boards following assembly.

We strongly recommend that the underside of the floor is treated an absolute minimum of twice. The floor bearers are pressure treated and don't need to be treated although you may if you wish. We also recommend that you seal the external corner joints (figC2) with silicone sealant (not supplied)

## Parts list

**PLEASE LAY OUT PARTS AND CHECK OFF AGAINST CHECK LIST BELOW:**

See drawings for log quantities. These details may be repeated in the drawing sheets.

BUILDING ASSEMBLY PARTS			QTY DESCRIPTION- CODE		
QTY	DESCRIPTION	CODE	QTY	DESCRIPTION-	CODE
<b>-sizes in mm unless stated</b>					
<b>FLOOR-</b>					
14	Pressure treated floor bearers 3380* (*may be joined, make sure you identify the deck bearers )		1	Middle inner 51x34x1368	WM
*9	pressure treated joiners-if bearers joined aprox.1m		4	Outer architrave 70x20x947	WC
31	Floor boards 110x20x3330		2	Outer architrave 90x20x1527	WD
3	Skirting 25x40x3400	SK	2	Outer architrave 70x20x1318	WE
1	Skirting 25x40x2300	SK	2	Centre architrave 51x20x847	WJ
1	Skirting 25x40x500	SK	1 set	Brass leaver handle set for doors	
<b>ROOF-</b>					
* Note the Angled eaves edging, Eaves fascia & roof edging may be supplied in shorter lengths.					
6	Packs shaped tiles		4 set	Brass leaver catches for windows	
18	Strips of eaves and ridge tiles		2	Door keys-taped to glazing bars	
5	Roof Bearers 44x145x 4090	RB1	22	Glazing- toughened 373mmx268mm	
4	Fascia boards 165x32x2050	FC	44	Short Beading	
2	Eaves (side) fascias 19x70x4090	SF	44	Long Beading	
2	Diamond		4	Casement stays with 2 pins and screw sets	
2	Angled eaves edging 44x24x 4090	AE	<b>TERRACE</b>		
2	Roof edging 44x70x 4090	RE	9	Pressure treated deck bearers 1500	
86	Roof boards 110x20x2000		12	Deck boards 3390	
<b>DOORS &amp; WINDOWS-</b>					
1	Pre hung external door	CODE	2	Terrace capping 95x20x 655	V11
4	window inserts	E-SD5	2	Terrace capping 95x20x1265	V14
4	Draught excluders -window 25x40x633	E-W4D-I	2	Corner cap 165x255	V12
4	Draught excluders -window 25x40x776		4	Terrace joiners 95x20x715	V13
2	window frame kits -taped in kits		<b>HARDWARE-</b>		
Qty per kit-see drawings before assembly					
2	inner frame upright 25x34x872	WA	8	100mm window hinges	
1	Bottom inner 25x34x1318	WB	112	25mm screws	
1	Top inner 25x34x1368	WT	140	40mm screws	
			336	50mm screws	
			52	80mm screws	
			176	Panel pins	
			780	Felt nails	
			64	25mm oval head nails	
			640	40mm round head nails	
			771	40mm oval head nails	
			12	75mm nails +36 if joiners used	

## IMPORTANT!

The only parts that require cutting are the angled eaves edgings , final roof and floor boards and the skirting.

**DO NOT CUT ANYTHING ELSE**

**A Windows– Inc frame assembly**

1. Refer to the two window drawing pages and to letter codes in contents table. The **WT** and **WD** parts will be at the top of the window frame.
2. To be sure you can lay all the pieces, including inserts together without fixing to familiarise yourself with the assembly.
3. Make sure the window insert fits inside the frame with a 5mm gap all around.
4. Lay out the parts **WA** and **WB** and **WT** as in the inner frame assembly drawing. The narrowest (25mm) edge to the work bench and the side the size is the same as the log thickness as shown in fig A1 . Part **WT** must be inside parts **WA** and part **WB** underneath the two **WA** parts (Fig A1 ) .
5. **WA** and part **WB** underneath the two **WA** parts (Fig A1 ) .
6. Pre drill 2 3mm holes at one end of the **WA** only and at both ends of the **WB** parts ( see drawing )and screw together at each corner,10mm in from the edge (ensuring each corner is flush) with 2x50mm screw (fig A1).




Fig A1

7. Measure and mark the centre of the frame (684mm from the outside fig A2 ) and position the **WM** piece (this is two pieces of wood already fixed side by side), Pre drill 2 3mm holes in the **WB** and **WT** parts and fix with 2x50mm screws at each end




Fig A2

8. Layout parts **WC**, **WD** , **WE** & **WJ** on top of the previous assembly as shown in the outer frame drawing.



Fig A3

9. Mark the first hole position 30mm from the end of part **WC** that is adjacent to the **WD** part , at the other end central to the **WB** part and then the between at approximately 260mm centres .
10. Note the **WC**, **WD** & **WE** pieces fitted to the opposite side must be drilled offset to this side to ensure the screws miss each other.
11. Place the other **WC** part underneath and drill through both pieces with a 3mm drill (fig A3).



Fig A4

12. Place one of the **WC** parts on top of the **WA** part level with the inside of the frame and the bottom of the **WT** part (fig A4).

13. Fix to part **WC** to **WA** with 40mm screws ,spaced as before. (fig A5 & A6)
14. **important** fix at both ends first ensuring that they stay flush then the screws in between again ensuring that parts **WA** & **WC** are flush as you go.



Fig A5




Fig A6

15. Place a **WD** part on top of a **WB** part. The **WD** part is positioned so there is an even overhang ( fig A7). Mark out and drill fix as before. But start at 100mm from the end of part **WD**.



Fig A7

16. Drill (not too deep) and screw in each corner with 40mm screws (fig A8).



Fig A8

17. With a pencil mark the screw centres on the inside long edge of the frame to help ensure the hinge screws will miss these screws.
18. Turn frame over and repeat on the other side fig A9 & A10).
19. **Note offset drilled holes from first side to ensure they miss each other first hole part **WC** =30mm part **WD** =100mm. LEAVE THE INNER SCREWS LOOSE SO YOU CAN REMOVE FRAME FROM THE BUILDING FOR PAINTING.**




Fig A9




Fig A10.

20. **Window insert.** Place one hinge on the inner rebate part of the window; approx. One hinge width along from the rebate edge of the longest edge of the insert. The rounded part of the hinge should sit above the outer edge of the window. Screw the inner piece into position ( fig. A11 &A12 ) using the pre drilled holes in the hinge and 3 x 25mm screws. Repeat with the other hinge. And close the hinges together.




Fig A10- STYLE MAY VARY



Fig A11

21. Place the window into the aperture (fig A12 ) **ensure that part WC** is against the hinges .  
 22. Secure the window to the frame using 3x 25mm screws per hinge, (fig. A13 ) again through the predrilled holes in the hinge.  
 23. Repeat.




Fig A12




Fig A13

24. Open the window fully in order to fit a further 2x 25mm screws per hinge ( Fig. A14 ).



1 Fig A14

25. **Fitting the draught excluder. This must be done before fitting the casement stays and latches.**



Fig A15

26. Lay the assembled window unit with the opening insert downwards onto your work surface (Fig A15).  
 27. Position the draught strips so the rubber is against the opening insert and fix with 3x25mm oval nails per strip (Fig A15).  
 28. At the bottom of each window place a casement stay on top of the draught excluder strip. Visually judge the position of the stay so it looks central. Use a pin to judge how high to position the stay. Fix using 2 x 25mm screws (Fig A16).




Fig A16

29. Stand the window up so it easier to fix the pins for the casement stays




Fig A17

30. Position the first pin so it fits into the first hole on the stay making sure it holds the window tight. Carefully remove the stay holding the pin in position, secure pin using 2 x 25mm screws (Fig A17) . Repeat for other pins.




Fig A18

31. Along side one of the horizontal bars on the window insert place the side latch on top of the draught excluder (Fig A18).  
 32. Use the pin to correctly place the lever and secure using 2x25mm screws for each part (Fig A18).




Fig A19

33. Fix the drip bar at the top of the window, there is a thin groove in one of the flat edges this needs to be facing the bottom of the building. Pre-drill seven holes and secure approx. 5mm above window inserts using 7 x 40mm screws.(figA19)

## B Floor bearers & first row of logs

See drawing pages **THE BEARERS DO NOT REQUIRE CUTTING**

Following the instructions below and with the help of the drawing pages assemble your building up to and including the gables





Fig B1 drawings needed

1. Use the contents list to identify all the bearer lengths. **Due to supply issues some bearers may be joined to make the total length. Place a joiner next to the bearers and fix as in step 2.**
2. Both the outer bearers are two bearers that sit side by side, nail these together with 70mm nails (at an angle) at approximately 300mm centres for each pair of bearers (fig B1).



Fig B2

3. Take the half height log (normally A1) that sit on the bearers and you see the bearer ends and mark the floor bearer centres, **but not the two pairs of outer bearers**, from one end (drawing page).



Fig B3

3. Place the 'A1' logs against each other and transfer all the lines across (fig B3).
4. The bearers stand with the narrowest edge to the floor (fig B4) and their ends 5mm back from the A1 logs face (Level with the chamfer).




Fig B4

5. Assemble the first row of logs on top of the bearers by placing the half height logs in position and then the first of the logs from each wall that run parallel to the bearers on top of them. (See section C4).
6. **The logs are assembled with the tongues upwards**
7. Position the outer bearers so the outer log sits 5mm in from the outer face (fig B5 and drawing page) of the side and front logs.




Fig B5

8. Cut notches out of the tongues on the A1 logs (fig B7) at centre marks (previous steps) and drill through for fixing to the bearers.
9. **Important**
10. Measure corner to corner, as building must be square
11. Also measure length at the centre of the building from wall to wall (A1 to A1) to ensure correct length before fixing to joists with 1x 80mm screw (figB6 & B7) at each bearer.




Fig B6



Fig B7

12. This is the bottom of all four walls now ready to be built upon.

## C Walls

See drawing pages

1. Using parts list for each wall layout correct quantity (fig C1) of each component for relevant wall (i.e. front, back) in suitable position for ease of assembly.




Fig C1-example

2. The walls can now be assembled as per drawing pages above. Start building walls by placing all the logs from front to back and then from side to side
3. **The logs are assembled with the tongues upwards**
4. Each log needs to be tapped home to log below using timber block supplied and a rubber mallet (C2).




Fig C2

silicone sealant to be applied after construction to the external joints shown with the arrow from top to bottom of the cabin

## D Inserting windows and doors

**AS SOON AS YOU FIT DOOR UNIT FIT HANDLES AND UNLOCK DOOR**

1. Door unit must be placed into position after the first two layers of full logs have been assembled
2. Slide unit into aperture from above (Fig D1 & D2) ensuring unit is completely down and in position.



Fig D1 EXAMPLE



Fig D2

- Window units are fitted as above (fig D38) when you have built up to the correct height



Fig D3 example

- Note** Door and window units do not require fixing to the logs
- Once the door and window units are in place continue assembling the walls as before but slide the logs into the door or window frame (fig D4) from above then tap them down.



Fig D4

- Continue building until you get to the height where the gable starts.

## E Gables

See drawing pages 3 & 5

- Assemble the gables as with the walls.
- Once gables are in place knock down all the walls again as in fig C2 to ensure all the walls are fully home
- Fix the gable with 1x80mm screw at each end (fig E1) and as shown on the drawing pages (Some screws may go into roof joists)




Fig E1

## F Roof joists

- Fit roof joists into slots provided in the gable sections (fig F1 & F2).



Fig F1

- Measure the distance between each roof joists and the roof joists and walls to ensure all components are fully home before continuing.



Fig F2 example

## G Roof boards

- There are eaves edging strips for the building (2 places) (These may need cutting to fit).
- Position the eaves edging strips (fig G1 & G2) level at both ends with the gable angle (front and back walls) and screw to the wall with 50mm screws at approximately 400 centres.



Fig G1



Fig G2

- The first roof board is now ready to be positioned (fig G3) **Bevel edge downwards. ( roof has flat surface where tiles fit )**
- NOTE** only the final boards need trimming .




Fig G3

- Start at the front, place the board level with the end of the roof joist and central over the middle bearer to produce an even overhang (fig G3).
- Fix into place at the roof bearers and angled eaves edgings using two 40mm ROUND HEAD nails at each bearer & eaves edging



Fig G4

- The final roof board will need to be cut. Place it in position and measure the distance between the end of the roof bearers and the edge of the board. This will tell you how much you need to cut off (fig G4).
- Next fit the roof edgings to the outer edges of the roof boards with 50 mm screws at approximately 300mm centres (Fig. G5).




Fig G5

- Fit the 19x70mm eaves edgings onto the roof edgings. Place a floor board on top of and over the edge of the roof as a guide and place the top of the roof edging level with this (fig G6) and fix with 40mm screws at 400mm spacing's.




Fig G6

## H Tile Roof

- Packs of shaped tiles and strips rectangular tiles for the eaves and ridge have been supplied. (SEE CONTENTS )
- Use tiles randomly from the packs of tiles supplied to even out the colour match.
- remove all dust and sharp edges from the roof boards.
- If you are fitting your own guttering fit it now so you can over lap the eaves tiles into the gutter.**



Fig H1

- Measure the length of the roof (fig H1) and mark the centre of the roof and repeat the other side .




Fig H2

- Lay out the row of ridge strips and shaped tiles and adjust the position of the tiles to get the least waste possible and if you can the piece that you trim off can be used at the other end.
- Place the first ridge strip so it is central to the mark (or your adjusted position) and over hanging the roof edging by 10mm.
- Measure the distance the tile is up the roof and mark it at either end of the roof. Tack the string at the marks at either end to use as a guide to keep the tiles level. (use this method to keep all your tiles square.
- remove the backing film and fit the row of eaves tiles. Nail the centre of each individual tile 1 cm down from the edge with one felt nail. (fig H2) and 2 nails at the bottom where they will be covered by the next tile layer.




Fig H3

- The installation of roofing shingles is usually started from the middle of the slope, so that the tabs of the shingles cover the end joints and perforations of the eaves shingles.
- The lower edge of the first row of shingles is aligned with the bottom edge of the eaves shingles, so that the line of the eave appears clean and straight when seen at an upward angle from the ground.
- The roofing shingles are fixed with roofing nails (4 pieces / shingle) as shown in the figures above, some 30 mm above the bottom of each notch along their centre lines.
- The shingles will bond to one another, but they are nailed to the roof.




Fig H4

- Use a sharp knife to trim the tiles level with the end of the roof. You should be able to use the excess piece on the other end of the roof.




Fig H5

- On the ridge, the topmost shingles are cut along the ridge line (not folded over the ridge!)(fig H5).
- By folding and tearing an eaves shingle as shown above (fig H5) you will have three ridge capping shingles.
- On a pitched roof, installation is started from either end so that the adhesive edge of the first ridge capping shingle is aligned along the verge, on top of the roofing shingles. The ridge capping shingle is nailed to the decking from the non-adhesive edge with four nails (two either side of the ridge).
- Ridge capping shingles are laid centrally on the ridge in such a way that the adhesive strip on the underside **overlaps** the previous sheet by some **50 mm** covering the nail heads. The procedure is repeated along the length of the ridge.

## I Fascia

- Fascia boards can now be drilled and screwed ( fig I1 ) with 1x 50mm screw at each roof bearer and the roof edgings.



Fig I1

- Drill diamond and screw with 2x50mm screws . (fig I2)




Fig I2

## J Floor

1. The floor is fitted working from front to back with 40mm nails
2. Position the first floorboard under the doorframe (Fig J1), with the **groove against the wall the bevel edge downwards**.



Fig J1

3. Fix into position with two nails at each floor bearer (Fig J2& J3).



Fig J2




Fig J3

4. Continue with remaining floorboards until you have three remaining.
5. Place these in position without nailing them down, as the last floorboard will require trimming.
6. Measure the distance between the last full board and the wall (Fig J4). This measurement is then marked on the final board and then cut to fit, **leaving the groove on the board**.




Fig J4

7. Curl the boards up ( fig J5 ) to put it into position and nail the remaining boards before



Fig J5

8. Cut the skirting boards to suit and fix with 40mm oval nails at approx 400mm centres (fig J6)



Fig J6

## K Terrace

1. Space the floor bearers as shown in the drawing pages, with the 63mm ( widest ) side to the floor and the outer bearers level with the walls (Fig K1)



Fig K1

2. Equally space the decking boards leaving an even gap between each board ,check that the deck is square and screw into position using 40mm screws (Fig K2 – K4)



Fig K2



Fig K3



Fig K4

3. Place the first row of logs into position (drawings), measure diagonally to ensure the logs are square and parallel before screwing into position ( as with the first row of building logs )with 80mm screws (Fig K5 –K7)



Fig K5




Fig K6




Fig K7

4. You are now ready to assemble the rest of the logs (Drawings & Fig K8)



Fig K8

5. Next four parts V13 (One inside and one outside at each joint) are used to join the veranda to the building (Fig K9) with 2 columns of four 40mm screws per V13.



Fig K9

6. Next position all the capping pieces (v11 front cap x2, v12 corner caps x4 & v14 side caps ) on top of the terrace.
7. Once you are happy with the positions you can fix them into place.
8. V11 & V14 into position (Fig K10) secure with 3 x 40mm screws each.
9. V12 corner caps secure with 4 x 60mm screws each.



Fig K10



Fig K11

10. (Fig K12) Shows the completed terrace.



Fig K12

## L Glazing

### After painting

1. **NOTE** ensure that you have treated the beading and the rebate where the glass fits before fixing the glazing.
2. Place glazing material into the aperture of each window.
3. Hold into position with four pieces of beading . The beading may need to be swapped around to get the best fit. When satisfied secure into position using 2x15mm panel pins per piece of beading . ( fig L1 )Repeat for all window and door apertures.



Fig L1

## Assembly Completion Checklist

1 Check and ensure that no raised grain or splinters are evident on timber components. Sand down any raised grain or splinters using fine grade sandpaper.

2 Check that all screw, nail and pin heads are properly tapped home and are not proud of the timber surface.

3 Check and ensure that no screws, nails or pins protrude through any panel.

4 Check and ensure that all parts are properly

secured against reasonable force.

5 Do not apply decorative wood finish/treatments to wet or damp timber. Please observe the instructions of the wood finish/treatment manufacturer.



# SHIRE

BUILT AROUND OUR REPUTATION

page 1

## Base details & Floor bearer layout

see page 2 for spacing




fig 1




Fig 2

Detail of log sitting on floor joists running parallel to floor bearers




Fig 3

Detail showing floorboard on joist

**Kinver 33**  
3590 X 3590(5090)  
34mm log



**FLOOR PLAN**

- Floor bearers 11 x 3380**
- Floorboards 31 x 3310**
- TERRACE FLOOR**
- Deck bearers 9x1500**
- Deck boards 12x3390**


# FRONT GABLE

# SHIRE

BUILT AROUND OUR REPUTATION



# Front view



# SHIRE

BUILT AROUND OUR REPUTATION

## page2

**Kinver 33**

3590 X 3590(5090)

34mm log

FRONT

Parts list

A1x 1

A2 x 1

C x 7

C1 x 1


D x 24

E x 8


bearer spacing

## BACK GABLE


14/04/2009



T SCREW HERE



# Back View



**SHIRE**  
BUILT AROUND OUR REPUTATION

pages 3

**Kinver 33**  
3590 X 3590(5090)

34mm log  
BACK  
Parts list

A x 17  
A1 x 1

# SHIRE

BUILT AROUND OUR REPUTATION

## LH side view

**Kinver 33**  
3590 X 3590(5090)

34mm log

LH SIDE

Parts list

A x 15

G x 1

H x 1

I x 1

Terrace

V1x3


V1tx1

V3x3

V6x3

capping  
v14

joiners  
v13x2



V13 OVERLAPS HERE

**Kinver 33**  
3590 X 3590(5090)


34mm log  
RH SIDE  
Parts list

- A x 8
- A3 x 1
- D x 6
- F x 8
- I x 1
- J x 1
- K x 1
- Terrace
- V1x3
- V1tx1
- V3x3
- V6x3
- capping
- v14
- joiners
- v13x2

# RH Side view

**SHIRE**  
BUILT AROUND OUR REPUTATION

pages








# Terrace front

Kinver 33  
3590 X 3590(5090)  
terrace

## PARTS LIST

- V2b x 2
- V2 x 4
- V2t x 2
- V6 x 24
- V6t x 2
- Capping
- V11 X 2
- V12 X 4



bearer spacing